



RADON TESTING INSTRUCTIONS FOR HOMEOWNERS:

Instructions taken from the EPA

CLOSED HOUSE CONDITIONS MUST BE MET:

- All external doors, windows, and vents should be kept closed from 12 hours before starting the test until the end of the test.
- You don't need to change your normal entry and exit routines, just make sure you close the door behind you.
- If the building has a permanently installed radon mitigation system, air to air heat exchanger, and/or combustion air supplies for furnaces, etc., they should be operated normally.
 - Do not operate any whole house or window fans during the test.

PLEASE NOTE: Device has motion sensor and will sense movement and airflow on the device.

Should you have any questions or concerns, please contact **En-Spect Environmental** by phone, text, or email.

